



Addendum to the Scope of works

Regarding the demolition sequence of works, after the excavation works of the slab on grade and prior to any demolition of any wall. A temporary support for the vault must be installed as follows

- 3 Wooden arches to be constructed at the vault ceiling, 1 at the start, 1 in the middle and 1 at the end of the Restroom, all across the long side.
- 2 steel props of 3" diameter to be installed to hold each wooden arch (total of 6 props for the restroom)
- The steel props to be installed on wooden plates on the new excavated level.
- 3 Wooden tie beams to be installed between the arches to hold them together

See Sheet AD-01 for more details on the temporary arch support

As for the Doorway demolition, the eastern wall demolition (relative to the plan north) has been minimized from 20cm to 5cm and the eastern wall of the doorway increased to 20cm of demolition as shown in sheet AD-02

Regarding the Door swing, it has been switched to swing to the right side instead of the left. As Shown in Sheet AD-03

The contractor has to submit shop drawings for his these temporary supports prior to any demolition works.